

Volume III - Price bid

MAHATMA MANDIR CONVENTION CENTER, GANDHINAGAR TENDER FOR UPGRADATION OF ACOUSTICS Volume III - PRICE BID					
Sr. No	Description	Unit	Appx. Qty	Rate	Amount
1	Providing & Fixing in position, Acoustical Panelling made from Fr grade Compressed Polyester 9 mm thick panels of Anutone / Technoacoustics or approved equivalent having density 200 kg/ cu m wrapped in FR grade decorative fabric, on, 40 x 40 mm Anodized Aluminium frame with chicken mesh on wall side (Or on existing base material), in front of 1000 Gsm synthetic wool 50 mm thick, (Excluding the cost of frame & synthetic wool), using screws and adhesive, including cost of required Cut-Outs, Groves, finishing-items & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. fabric base rate 450 / sq. m	Sq m	2250		
2	Providing & Fixing in position, Acoustical Panelling made from Fr grade flexible, open-cell melamine polymer foam 50 mm thick panels having density 9 kg/ cu m laminated with FR grade decorative fabric, on, 40 x 40 mm Anodized Aluminium frame with chicken mesh on wall side (Or on base material), in front of 1000 Gsm synthetic wool 50 mm thick, (Excluding the cost of frame & synthetic wool), using the OEM adhesive, including cost of required Cut-Outs, Groves, finishing-items & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. fabric base rate 450 / sq. m	Sq m	1450		
3	Providing & Fixing in position, 40 x 40x 3 mm Anodized Aluminium frame 600 x 600 c to c having supports of required lengths from wall not less than 2400 mm c to c with chicken mesh on wall side, having infill of 1000 Gsm synthetic wool 50 mm thick, (Excluding the cost of synthetic wool), using screws and accessories, including cost of Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects.	Sq m	2500		
4	Removal of existing gypsum wall panelling, false ceiling & its framing along with infill and supports & disposing it properly.	Sq m	7500		
5	Removal of fabric from wall panelling & disposing it properly.	Sq m	1000		
6	Providing & Fixing in position, Thermally bonded Fr grade Synthetic Wool 50 mm thick 1000 gsm make Mikron/ Anutone/ Reliance, as overlay on the T grid tiles or as infill with Aluminium frame with chicken mesh backing, as per Architectural & Acoustical Design & Instructions & Complete in all aspects.	Sq m	5000		

Volume III - Price bid

Volume III - PRICE BID

Sr. No	Description	Unit	Appx. Qty	Rate	Amount
7	<p>Providing & Fixing in position, Acoustical Ceiling made from Ecophone Advantage E/ Armstrong Optra / Anutone Subtex/ Knauf AMF TOPIQ® Efficient pro 15mm compressed Soft fibre Bevelled Tegular Edge tiles on OEM 15 mm exposed Silhouette (Grove) profile T grid with black grove, Having 50mm GI "C" channel white painted border on periphery, suspended with OEM Hangers from the structure as per OEM specifications, with overlay of FR grade 1000 Gsm synthetic wool 50 mm thick, The tiles should have Humidity Resistance (RH) of 95%, NRC 0.9 - 1.0, Light Reflectance ≥85%, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 15mm , with Recycled content of 66% GW. The tile shall be laid on OEM Silhouette profile grid system with 15mm white flanges incorporating a 6mm central reveal in black colour and with a web height of 45mm and a load carrying capacity of minimum 15.68 Kgs/M2 & pull out strength of 100Kgs. Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with OEM Suspension system, including cost of required Cut-Outs, finishing-items & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects.</p>	Sq m	2500		
GROSS TOTAL					
Notes-Remarks :-					
1	Related payment shall be made on the basis of actual work executed on site and certified by Employer/Engineer-in-Charge. Qty. mentioned above is indicative and it may increase or decrease according to the requirements of the project. All measurements to be taken jointly with Employer /Engineer-in-Charge.				
2	Selected bidder is bound to execute the works as per time line given by client/iNDEXTb.				
3	Price bid shall be filled up on line on n-procure by selected/empanelled agencies. Works will be allotted to the lowest bidder as approved by iNDEXTb. Decision of the iNDEXTb shall be final in any matters.				
4	All duties, custom duties, taxes (including all Central excise tax, Central Govt. & all state Govt. taxes if any.) and other levies payable by the Contractor and shall be included in the Rates and Prices and the total bid price submitted by the bidder. No taxes shall be paid separately.				
5	Rates quoted include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture, weather etc.				
6	The Bidder has to execute at his own cost, if existing structure will be damaged during execution of works. No additional claim will be payable but the Bidder has to complete damaged work in its original state.				
7	Where there is discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern.				

Volume III - Price bid

Volume III - PRICE BID

Sr. No	Description	Unit	Appx. Qty	Rate	Amount
8	If the total amount of bid quoted is less than actual summation of cost of all the components/parts as the case may be, then the total quoted amount shall govern and difference between actual summation and amount quoted shall be considered as a discount.				
9	If total amount of bid is more than actual summation of cost of all components/parts as the case may be, then the individual cost of the components/parts shall govern and total amount shall be reduced to actual summation and it shall be considered as mistake in totaling.				
10	Where there is discrepancy between the rates in figures and in words, whichever is less shall govern.				